

WESTERN SPINDLE LLC TEST REPORT

SCOPE OF WORK

STRUCTURAL PERFORMANCE TESTING ON THE 12 FOOT BY 42 INCH URETHANE
BALUSTRADE SYSTEM

REPORT NUMBER

80916.02-119-19 R0

TEST DATE

04/11/08

ISSUE DATE

09/24/18

RECORD RETENTION END DATE

04/11/13


PAGES

13

DOCUMENT CONTROL NUMBER

RT-R-AMER-Test-2846 (02/09/18)

© 2017 INTERTEK



TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

REPORT ISSUED TO

WESTERN SPINDLE LLC

310 6th Street

Townsend, MT 59644

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by Haas Architectural Millwork, Inc., 165 South Orchard Street, Red Lion, Pennsylvania 17356 to perform structural performance testing in accordance with the 2006 IBC and 2006 IRC on the 12 foot by 42 inch urethane balustrade system. All tests performed were to evaluate structural performance of the guardrail assembly to carry and transfer imposed loads to the supporting structure. The test specimens evaluated included the infill, rails, rail brackets, and support posts. Anchorage of support posts to the supporting structure is not included in the scope of this testing and would need to be evaluated separately.

Results obtained are tested values and were secured by using the designated test methods. Testing was conducted at the Intertek B&C test facility in York, Pennsylvania. This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

This report is reissued in the name of Western Spindle LLC through written authorization of Haas Architectural Millwork, Inc. to whom the original report was rendered. The original Haas Architectural Millwork, Inc. Report No. is 80916.01-119-19.

For INTERTEK B&C:

| | |
|----------------------|---------------------|
| COMPLETED BY: | Scott T. Gladfelter |
| TITLE: | Project Engineer |
| SIGNATURE: | |
| DATE: | 09/24/18 |

STG:tah/aaa

| | |
|---------------------|------------------|
| REVIEWED BY: | Travis A. Hoover |
| TITLE: | Program Manager |
| SIGNATURE: | |
| DATE: | 09/24/18 |

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

SECTION 2

SUMMARY OF TEST RESULTS

The specimens met the 2006 IBC design load performance requirements.

Limitations

All tests performed were to evaluate structural performance of the guardrail assembly to carry and transfer imposed loads to the supporting structure. The test specimens evaluated included the in-fill (balusters), rails, rail brackets, and support posts. The support posts were not a tested component and were included in the test specimen only to facilitate anchorage of the rail brackets.

SECTION 3

TEST METHODS

The specimen was evaluated in accordance with the following:

2006, *International Building Code*[®], International Code Council

2006, *International Residential Code*[®], International Code Council

SECTION 4

MATERIAL SOURCE/INSTALLATION

Haas Architectural Millwork, Inc. provided the fully-assembled PVC guardrail system test specimens: top rail, bottom rail, balusters (in-fill), rail brackets, fasteners, posts, and support blocks.

The guardrail was tested in a self-contained structural frame designed to accommodate anchorage of the guardrail assembly and application of the required test loads. The specimens were loaded using an electric winch mounted to a rigid steel test frame. High strength steel cables, nylon straps, and load distribution beams were used to impose test loads on the specimens. Applied load was measured using an electronic load cell located in-line with the loading system. Electronic linear motion transducers were used to measure deflections. See photographs in Section 10 for individual test setups.

Representative samples of the test specimens will be retained by Intertek B&C for a minimum of four years from the test completion date.

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

SECTION 5

LIST OF OFFICIAL OBSERVERS

| NAME | COMPANY |
|------------------|--------------|
| Keith A. Gurnee | Intertek B&C |
| Travis A. Hoover | Intertek B&C |

SECTION 6

TEST SPECIMEN DESCRIPTION

Haas Architectural Millwork, Inc. provided the test components with the following details:

Top Rail: 5.550 in wide by 4 in high, low density, polyurethane foam contoured profile with 2.875 in O.D. by 0.225 in wall thickness PVC pipe internal support

Bottom Rail: 5.625 in wide by 4 in high, low density, polyurethane foam flat-top contoured profile with 2.875 in O.D. by 0.225 in wall thickness PVC pipe internal support

Brackets: 3 in wide by 2.5 in high aluminum "L" bracket with 0.188 in wall thickness

Balusters: 2.5 in square by 32 in long, low density, polyurethane foam spindle with 1.0 in O.D. by 0.125 in wall thickness PVC pipe internal support

Posts: 5.5 in square, low density, polyurethane foam newel profile with 4.5 in O.D. by 0.250 in wall thickness PVC pipe internal support

Fastening Schedule

| | |
|---|--|
| Top Rail Bracket to Post ¹ | Two 1/4-20 x 1-1/2 in hex-head bolts with washers and nuts |
| Bottom Rail Bracket to Post ¹ | Two 1/4" x 2" pan-head, zinc-plated screws |
| Top Rail to Aluminum Bracket | Two 1/4" x 2" pan-head, zinc-plated screws |
| Bottom Rail to Aluminum Bracket | One 5/16-18 x 1-1/4" hex-head bolt |

¹Rail to post fastener assemblies were reinforced with adhesive.

See drawings in Section 11 and photographs in Section 10 for additional details.

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

SECTION 7

TEST PROCEDURE

Each test specimen was inspected prior to testing to verify size and general condition of the materials, assembly, and installation. No potentially compromising defects were observed prior to testing.

The 12 ft wide by 42 in high guardrail assembly was installed and tested as a single railing section by directly securing the posts into a rigid steel test fixture, which rigidly restrained the posts from deflecting. Transducers mounted to an independent reference frame were located to record movement of reference points on the guardrail system components (ends and mid-point) to determine net component deflections. See photographs in Section 10 for individual test setups.

An initial load, not exceeding 50% of design load, was applied and transducers were zeroed. Load was then applied at a steady uniform rate until reaching 2.0 times design load in no less than 10 seconds. After reaching 2.0 times design load, the load was released. After allowing a minimum period of one minute for stabilization, load was reapplied to the initial load level used at the start of the loading procedure, and deflections were recorded and used to analyse recovery. Load was then increased at a steady uniform rate until reaching 2.5 times design load or until failure occurred. The testing time was continually recorded from the application of initial test load until the ultimate test load was reached.

SECTION 8

TEST RESULTS

The following tests were performed on the guardrail assemblies for the design load requirements of the codes referenced. Deflection and permanent set were component deflections relative to their end-points; they were not overall system displacements. All loads and displacement measurements were horizontal, unless noted otherwise.

Key to Test Results Tables:

| | |
|-----------------------------|---|
| <u>Load Level:</u> | Target test load |
| <u>Test Load:</u> | Actual applied load at the designated load level (target). Where more than one value is reported, the test load was the range (min.-max.) that was held during the time indicated in the test. |
| <u>Elapsed Time (E.T.):</u> | The amount of time into the test with zero established at the beginning of the loading procedure. Where more than one value is reported, the time was the range (start-end) that the designated load level was reached and sustained. |

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

| Test No. 1 - 04/11/08 | | | | | | |
|---|----------------|-------------------|-------------------|------|------|------------------|
| Design Load: 50 lb / 1 Square Ft at Center of In-Fill (on Two Pickets) | | | | | | |
| Load Level | Test Load (lb) | E.T. (min:sec) | Displacement (in) | | | |
| | | | End | Mid | End | Net ¹ |
| Initial Load | 20 | 00:00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2.0x Design Load | 107 | 02:03 | 1.09 | 1.30 | 1.05 | 0.23 |
| Initial Load | 20 | 04:37 | 0.35 | 0.39 | 0.35 | 0.04 |
| 2.5x Design Load | 125 | 07:07 | 83% Recovery | | | |

¹ Net displacement was the picket displacement relative to its top and bottom.

| Test No. 2 - 04/11/08 | | | | | | |
|---|----------------|-------------------|-------------------|------|------|------------------|
| Design Load: 50 lb / 1 Square Ft at Bottom of In-Fill (on Two Pickets) | | | | | | |
| Load Level | Test Load (lb) | E.T. (min:sec) | Displacement (in) | | | |
| | | | End | Mid | End | Net ¹ |
| Initial Load | 20 | 00:00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2.0x Design Load | 100 | 00:21 | 0.07 | 1.24 | 0.07 | 1.17 |
| Initial Load | 25 | 03:40 | 0.02 | 0.27 | 0.01 | 0.26 |
| 2.5x Design Load | 125 | 04:38 | 78% Recovery | | | |

¹ Net displacement was the bottom rail displacement relative to its ends.

| Test No. 3 - 04/11/08 | | | | | | |
|--|-------------------|-------------------|------------------------|-------|------|------------------|
| Design Load: 50 plf x (144 in ÷ 12 in/ft) = 600 lb Horizontal Uniform Load on Top Rail ¹ | | | | | | |
| Load Level | Test Load (lb) | E.T. (min:sec) | Rail Displacement (in) | | | |
| | | | End | Mid | End | Net ² |
| Initial Load | 140 | 00:00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 1.67x Design Load | 1008 ³ | 03:55 | 0.39 | 10.78 | 0.46 | 10.36 |
| Initial Load | 154 | 06:26 | 0.06 | 2.16 | 0.08 | 2.09 |
| 2.5x Design Load | 1534 | 08:09 | 80% Recovery | | | |

¹ Uniform load is simulated with 1/4-point loads.

² Net displacement was mid-rail displacement relative to the rail at the support posts.

³ The testing was stopped short of the 2.0x design load; therefore recovery value is based on 1.67x design load.

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

SECTION 9

CONCLUSION

Using a performance criteria of 75% deflection recovery from 2.0 times design load (with exception as noted in Test No. 3) and withstanding an ultimate load of 2.5 times design load, the test results substantiate compliance with the design load requirements of the referenced building codes for the 12 ft wide by 42 in high railing assembly.

The railing supports were not included within the scope of this testing, and these conclusions would apply only for a railing that is provided with adequate supports that provide equal or better substrate material for the fasteners used to anchor the rail brackets.

Anchorage of support posts to the supporting structure is not included in the scope of this testing and would need to be evaluated separately.

SECTION 10

PHOTOGRAPHS



Photo No. 1

In-Fill Load Test at Center of Two Balusters

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18



Photo No. 2
In-Fill Load Test at Bottom of Two Balusters



Photo No. 3
Horizontal Uniform Load Test of Top Rail

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18



Photo No. 4
Top and Bottom Rail Profiles



Photo No. 5
Top Rail - Bracket - Post Connection

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18




Photo No. 6

Bottom Rail - Bracket - Post Connection

SECTION 11 **DRAWINGS**

The "As-Built" drawings for the 12 foot by 42 inch urethane balustrade system; which follow have been reviewed by Intertek B&C and are representative of the project reported herein. Project construction was verified by Intertek B&C per the drawings included in this report. Any deviations are documented herein or on the drawings.




Architectural Testing

Test sample complies with these details.
Deviations are noted.

Report # 80916.01

Date 7/23/13 Tech 7/1



SECTION 01
SCALE: 1/2" = 1'-0"

ELEVATION 02
SCALE: 1/2" = 1'-0"



HAAS ARCHITECTURAL MILLWORK
27 Grand St. Red Lion, PA 17356
Phone: (717) 246-6290 | Fax: (717) 246-6291
Email: haasmillwork@haasmillwork.com
Visit us on the web at www.haasmillwork.com


PART NAME HTR 204-12; HBR 205-12; HNP 300-6; HBAL 103-32
PART NUMBER
PROJECT Haas Architectural Millwork

ALL ITEMS ARE DRAWN FOR PRESENTATION PURPOSES ONLY, THEREFORE IMAGE SHOWN MAY VARY SLIGHTLY FROM FINISHED ACTUAL PART. DRAWING SHOWN IS TO INDICATE GENERAL ARRANGEMENT AND DESIGN. HAAS ARCHITECTURAL MILLWORK RESERVES THE RIGHT TO CHANGE ANY PRODUCT DESIGN WITHOUT NOTIFICATION.


REV. 1 1-25-2013
REV. 2 7-18-2013
REV. 3 7-19-2013
REV. 4
REV. 5
REV. 6

DRAWING NO. 1 1 0

Top
Bracket



Bottom
Bracket



Width of bracket - 3"



Test sample complies with these details.
Deviations are noted.

Report # 80916.01

Date 7/23/13 Tech 716

SECTION 01
SCALE: 6" = 1'-0"

ELEVATION 02
SCALE: 6" = 1'-0"

haas

HAAS ARCHITECTURAL MILLWORK
27 Grand St. Red Lion, PA 17356
Phone: (717) 246-6290 | Fax: (717) 246-6291
Email: haasmillwork@haasmillwork.com
Visit us on the web at www.haasmillwork.com

| | | | | |
|---|-----------------------------|--------|-----------|-------------|
| PART NAME | HRK Parts | REV. 1 | 1-25-2013 | DRAWING NO. |
| PART NUMBER | | REV. 2 | | 1.0 |
| PROJECT | Haas Architectural Millwork | REV. 3 | | |
| ALL ITEMS ARE DRAWN FOR PRESENTATION PURPOSES ONLY, THEREFORE IMAGE SHOWN MAY VARY SLIGHTLY FROM FINISHED ACTUAL PART. DRAWING SHOWN IS TO INDICATE GENERAL ARRANGEMENT AND DESIGN. HAAS ARCHITECTURAL MILLWORK RESERVES THE RIGHT TO CHANGE ANY PRODUCT DESIGN WITHOUT NOTIFICATION. | | REV. 4 | | |
| | | REV. 5 | | |
| | | REV. 6 | | |
| | | | | |



Total Quality. Assured.

130 Derry Court
York, Pennsylvania 17406

Telephone: 717-764-7700
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR WESTERN SPINDLE LLC

Report No.: 80916.02-119-19 R0

Date: 09/24/18

SECTION 12

REVISION LOG

| REVISION # | DATE | PAGES | REVISION |
|------------|----------|-------|--|
| 0 | 09/24/18 | N/A | Original Report Issue - Changed Report No. 80916.01-119-19 to reflect company name change from Haas Architectural Millwork, Inc. to Western Spindle LLC. |